

Full Depth Reclamation Bid items:

	Unit	Unit \$
1) Full Depth Reclamation 12" deep Test Strip (10' x 300')	LS	\$_____
2) Full Depth Reclamation 12" deep with Cement additive, including compaction and grading (20,000 SY)	SY	\$_____
3) Cement for FDR (assume 1.5% of unit wt. or approx. 50lb/CY in design mix for pricing. Exact quantity TBD following mix design	TON	\$_____
4) Prime & Sand (20,000 SY)	SY	\$_____
5) FDOT AC SP 12.5 (1-1/2" over 20,000 SY)	TON	\$_____
6) FDOT AC SP 9.5 (1-1/2" over 20,000 SY)	TON	\$_____
7) 4" Yellow Paint (1,455 LF)	LF	\$_____
8) 4" Blue Paint (1,213 LF)	LF	\$_____
9) 4" Red Paint (637 LF)	LF	\$_____
10) Survey, stake out (assume 3 days)	Day	\$_____
11) Geotechnical Investigation/Mix Design	LS	\$_____
12) Mobilization	LS	\$_____

TOTAL COSTS-----\$\_\_\_\_\_

BIDDER \_\_\_\_\_